

TOWN OF SOUTHWEST RANCHES, FLORIDA
Southwest Ranches Drainage Project
IFB No. 19-002
Tuesday, April 16, 2019

ADDENDUM 2

1. **Question:** What is the estimated budget for the project?

Answer: The estimated budget for the project including professional services fees and construction fees is \$400,000.

2. **Question:** Should the US Foundry grates be priced as galvanized or painted?

Answer: Engineer/Town does not have a preference between steel painted or steel galvanized grates. However, all grates shall be H-20 traffic loading.

3. **Question:** PRB's should be included on all itemized bid forms and not just shown on the plans and details.

Answer: PRBs are an incidental item that needs to be included as part of the cost of the inlets.

4. **Question:** What is the type of root barrier for work element 2?

Answer: ITEM 3 - CUT BACK EXISTING ROOTS AND INSTALL ROOT BARRIER shall be revised as follows:

The work covered by this item shall include, but not be limited to, the cutting, removal and disposal of the existing tree roots and the complete installation of a root barrier in accordance with the contract documents.

The cutting of the existing roots shall be performed under the supervision of a Certified Arborist. The root barrier shall extend vertically from 6" above the top-of-pipe to 6" below the invert of the pipe.

The following root barrier products shall be acceptable: DeepRoot Tree Root Barrier as manufactured by Deep Root Green Infrastructure, LLC; Vespro Root Barrier as manufactured by Vespro, Inc.; Root Solutions Root Barrier as manufactured by Tournesol Site Works; Root Barrier Panels as manufactured by Century Products; or an approved equal product.

5. **Changes in tentative schedule of events:**

Event	Date
Deadline for Request for Clarification	Friday, April 19, 2019 @ 12:00 noon
Bids Due / Opening of Bids	Friday, April 26, 2019 @ 11:00 a.m.