

Bid To Town of Southwest Ranches

Town of Southwest Ranches
13400 Griffin Road
Southwest Ranches, FL 33330

Gentlemen:

The undersigned, as Bidder, hereby declares that the only persons, company, or parties interested in the Bid or the Contract to be entered, as principals, are named herein; and that this Bid is made without connection with any other person, company, or parties making a Bid; and that it is in all respects fair and in good faith without collusion or fraud.

The Bidder has carefully and to his full satisfaction examined any and all information the Bidder deems necessary to submit this Bid, including but not limited to, the attached Instructions to Bidders, General Conditions, Supplementary Conditions, Technical Specifications, and Contract and Bonds, together with the accompanying Drawings, Project Specifications and that he has read all addenda issued prior to the opening of Bids; and that he has made a full examination of the location of the proposed Work and hereby agrees to furnish, unless otherwise provided, all implements, machinery, equipment, transportation, tools, materials, supplies, labor, and other things necessary to the prosecution and completion of the Work generally described as follows:

Provide labor and equipment required to construct the proposed improvements for the Town of Southwest Ranches Town Hall Improvements project (Invitation For Bid (IFB) # 23-005). The Town is looking to repair and replace the existing Town Hall parking lot. Improvements include regrading to address ponding, replacement of curbing, adding flumes, drainage structures and associated piping and connecting roof drain downspouts to the drainage system. All labor, equipment, and materials necessary to construct the improvements described by these Drawings and Project Specifications will be provided by the contractor. Construction of this Project will require close coordination with the Town and Engineer.

It is proposed that the Project herein described shall be constructed for the Total Bid Amount based on the Contract Unit Prices in this Bid, all in accordance with the requirements and provisions of the Contract Documents. The Town at its sole discretion shall award this Contract based on the Total Bid Amount, and in accordance with **Section 16** (Award of Contract) in the Instructions to Bidders.

143221000

BID FORM

The following Bid Form is presented to assist the Town in evaluating the Bid. This Bid Form reflects estimated quantities for the Total Bid as described above. After award, the Town reserves the right to modify estimated quantities subject to the unit price and eliminate line items if necessary. Payment shall be made for the items listed on the Bid Form based on the Work performed and completed.

<u>Bid Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Value</u>
GC-1	Mobilization	1	LS		
GC-2	Maintenance of Traffic	1	LS		
GC-3	Stormwater Pollution Prevention Plan	1	LS		
GC-4	Site Restoration	1	LS		
Demolition					
DE-1	Trench Excavation	780	CY		
DE-2	Mill Existing Asphalt (1.5" Avg Depth)	2,500	SY		
DE-3	Remove Existing Type 'D' Curb	550	LF		
DE-4	Remove Existing Concrete	130	SY		
DE-5	Remove Existing Speed Bump	2	EA		
DE-6	Root Pruning	185	LF		
DE-7	Clear Earthwork	50	SY		
Site Improvements					
C-1	8" Limerock Base	150	SY		
C-2	Asphaltic Concrete Surface Course Overlay, FDOT Type SP-9.5 (1.5" Minimum)	2,500	SY		
C-3	Concrete Pavement (4" Depth)	100	SY		
C-4	Concrete Pavement (6" Depth)	50	SY		
C-5	CR-A Ramp	1	EA		
C-6	Sod	200	SY		
C-7	Type 'D' Curb	550	LF		
C-8	Wheel Stop	20	EA		

PM-1	6" Solid White	576	LF		
PM-2	Special Emphasis Crosswalk	1	LS		
PM-3	Handicap Parking Stall	2	EA		
PM-4	24" Solid White Stop Bar	1	EA		
PM-5	Detectable Warning Mat	70	SF		
PM-6	Speed Bump	2	EA		
DR-1	Catch Basin	3	EA		
DR-2	Rainwater Leader Connections	6	EA		
DR-3	Reflective Pavement Marker (RPM)	180	LF		
DR-4	18" HDPE	180	LF		
L-1	Root Barrier	185	LF		
Miscellaneous					
A-1	Allowance	1	LS	\$15,000	\$15,000
SUBTOTAL					
TOTAL					

TOTAL BID AMOUNT \$ _____

TOTAL BID AMOUNT (IN WORDS) _____

TOTAL BID AMOUNT \$ _____

TOTAL BID AMOUNT (IN WORDS) _____

The following Bid Item Notes apply to all bid items:

1. Bid Item GC-1 is a lump sum pay item for all mobilization costs.
2. Bid Item GC-2 is a lump sum pay item for a Maintenance of Traffic and includes all pedestrian access maintenance. All crosswalks and sidewalks shall remain open and free of obstructions. Temporary painting for roadways and crosswalks shall be maintained throughout the project. Costs shall include the use of flagmen, if required.

3. Bid Item GC-3 is a lump sum pay item to furnish, install, and maintain the complete storm water pollution prevention plan (SWPPP). Costs shall include but not be limited to all baled hay, filter fabric, silt fence, sediment inlet barriers, turbidity barriers, Notice of Intent fees, and compliance with any SWPPP reporting.
4. Bid Item GC-4 is a lump sum pay item that includes the complete restoration of the project site impacted by any construction activity including but not limited to mobilization, clearing and grubbing, striping removal, milling and resurfacing, asphalt, limerock, and base removal, limerock rework, asphalt overlay, utility adjustments, etc. Any swale areas impacted by the contractor outside of those indicated on the plans will be restored by the contractor at no additional cost to the Town. The pay item includes but is not limited to sod, landscaping, trees, excavation, new fill, limerock base preparation, grading, tamping, irrigation, driveway aprons (asphalt, pavers, stamped concrete, etc.), sidewalks, fences, pipes, curbs, etc. to an equal or better condition prior to construction. The contractor shall include the costs associated with a preconstruction video to confirm existing conditions. Any damage not confirmed by preconstruction video will be repaired at no additional cost to the Town.
5. Bid Item DE-1 includes all labor and equipment costs associated with trench excavation for stormwater structure and pipe installations, median installation,
6. Bid Item DE-2 includes all labor and equipment costs associated with milling the existing asphalt throughout the project area as shown on the plans. Price and payment shall be made at the contract unit price per square yard of existing asphalt milled (minimum depth 1.5") prior to placing the asphalt concrete overlay, hauling and removal of debris, and surface preparation. Any first lift of asphaltic concrete installed as part of a separate bid item must be placed so that it is not impacted or removed as part of this proposed milling process.
7. Bid Item DE-3, DE-4, DE-5, DE-6, and DE-7 includes all labor and equipment costs associated with removing the listed features, hauling and removal of debris and surface preparation.
8. Bid Item C-1 includes all material, labor, and equipment costs associated with partial pavement restoration. The costs include saw cutting, removal of asphalt, all associated excavation, management of excavated materials, reworking of limerock (8" minimum), backfill and compaction, testing, and restoring asphalt (1" minimum) to match existing grade prior to the final overlay as shown on the plans. All costs associated with the final overlay shall be included in Bid Item C-2.
9. Bid Item C-2 includes all material, labor, and equipment costs associated with installing the asphalt concrete overlay (1" or 2") throughout the project area as shown on the plans complete and accepted. This resurfacing bid item includes costs to provide a smooth and continuous grading throughout the entire asphalt overlay process to avoid areas of standing water.
10. Bid Item C-3 and C-4 includes all material, labor, and equipment costs associated with installing the concrete pavement (4" or 6") throughout the project area as shown on the plans complete and accepted, as per FDOT Index 522-001.
11. Bid Item C-5 includes all material, labor, and equipment costs associated with the installation of a CR-A Curb as per FDOT Index 522-002.
12. Bid Item C-6 includes all material, labor, and equipment costs associated with sodding the landscape island as depicted on the plans.
13. Bid Item C-7 includes all material, labor, and equipment costs associated with the installation of a Type 'D' Curbing as per FDOT Index 520-001.
14. Bid Item C-8 includes all material, labor, and equipment costs associated with the installation of a Wheel Stops.
15. Bid Items PM-1, PM-2, PM-3, and PM-4 include all costs associated with installing signage, reflective pavement markers, and thermoplastic pavement markings including temporary pavement markings prior to thermoplastic. This bid item shall also include existing striping removal through water-blasting, if necessary. Costs associated with replacing existing signs or traffic control devices damaged because of construction will be the responsibility of the contractor.
16. Bid Items PM-5 and PM-6 include all costs associated with installing Speed Bumps and Detectable Warning Mats as depicted in the plans.
17. Bid Items DR-1, DR-2, DR-3, and DR-4 include all costs associated with installing the stormwater system as depicted in the plans.
18. Bid Items L-1 include all costs associated with installing Root Barriers as depicted in the plans.

END OF SECTION

143221000